

SEP 08 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>47N</u> R <u>44W</u>	<u>K-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register's Office }
Gogebic County } ss.

Received for record the
14th day of MAY

A. D. 1998 at 3:20 o'clock
P m., and recorded in
Liber 6 of CORNERS
on page 373

Ramona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

Section Corner 1, 2, 11 & 12; T.47 N., R.44 W.

I, Richard L. Drahn in a field survey on April 28, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by William Burt in 1848. Original B.T.s --- Y. Birch 14" N.25 W. 37 links (24.42') --- Cedar 14" S.70 E. 14 links (9.24') --- Corner restored by Richard L. Drahn (21564) on 8/5/81 from the remains of the two original B.T.s and from a natural feature tie and a line tree. He set a 2" X 30" aluminum pipe with a 3 1/2" stamped aluminum pipe and the following:

16"	Sugar Maple	N.88 W.	18.58'
14"	Sugar Maple	N.15 E.	39.32'
11"	Sugar Maple	S.10 E.	16.23'
6'	Steel sign rail	N.50 W.	2.3'

Corner recorded in Gogebic County Liber 2, Page 250 on 3/10/82.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner research on file with Gogebic County records.

Recovered the monument as described and the bearing trees as follows:

19"	Sugar Maple	N.89 W.	18.62' (tree has been cut)
17"	Sugar Maple	N.18 E.	39.12' (new nail)
15"	Sugar Maple	S.06 E.	16.25'
6'	Steel sign rail	N.53 W.	2.3'

A stump hole from the Yellow Birch is all that remains of the GLO B.T.s. 1992 B.T. by John R. Garske (28410) 8" Sugar Maple S.44 W. 21.57'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing trees referenced:

6"	Sugar Maple	N.67 W.	45.34'
10"	Sugar Maple	S.47 W.	21.56'

PEER GROUP APPROVED
Richard L. Drahn 5/13/98
COUNTY REPRESENTATIVE



Signed by Richard L. Drahn

Date May 3, 1998

Surveyor's Michigan License No. 21564