

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office } ss.  
Gogebic County }

For corners in  
Gogebic  
(County)

Received for record the  
19<sup>th</sup> day of JANUARY  
A. D. 1993 at 9:35 o'clock  
A m., and recorded in  
Liber 4 of CORNERS  
on page 299

Betty Sassi Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

1. Public Land Survey	T <u>47N</u> R <u>44W</u>	<u>K-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

**PEER GROUP** Approved

4. Lot No. \_\_\_\_\_, Recorded Plat Richard P. Dredon 1/20/94  
5. Private Claims \_\_\_\_\_

One-quarter corner, Sections 11 & 12, T47N, R44W.

I, John R. Garske, in a field survey on December, 19 92, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Original Town Survey by William and Austin Burt, Deputy Surveyors, Aug.-Sept., 1847.  
Original corner set by William Burt, 1848.

Original Bearing Trees:  
Hemlock - 8" - S20°W - 5 links  
Hemlock - 8" - N60°E - 11 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I set a mathematical point at the proportional position from which to search and found no evidence of the original bearing trees. The corner location falls on an old blue painted line. A small post bears N30°W, 30± from our position. I set the corner at the math point due to a lack of any other evidence to position the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set a 2 1/2" x 30" long aluminum pipe with a 3" diameter tablet stamped to read: 1/4 corner, S-11, S-12, T47N, R44W, 1992; RLS 28410. Established the following bearing trees and/or reference objects:

- 8" maple - N69°E - 13.34 feet
- 10" maple - N15°W - 14.38 feet
- 5" maple - S24°W - 6.73 feet
- 6' steel rail w/sign - N45°E - 2.18 feet

Signed by John R. Garske  
Surveyor's Michigan License No. 28410

Date 1/20/94



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983