

SURVEY &
REMONUMENTATION

SEP 08 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

For corners in SECTION

Gogebic (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>47N</u> R <u>44W</u>	<u>K-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Received for record the
14TH day of MAY
A. D. 1998 at 3:20 o'clock
P m., and recorded in
Liber 6 of CORNELIS
on page 375.
Ramona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

$\frac{1}{2}$ Corner 13 & 14; T.47 N., R.44 W.

I, Richard L. Drahn in a field survey on April 23, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Corner established by William Burt in 1848. Original B.T.s --- Y. Birch 12" N.30 E. 36 links (23.76') --- Hemlock 12" S.10 W. 27 links (17.82') ---
Corner position re-established by John B. Garske (28410) on 5/21/92 by single proportionate methods. He set a 2 $\frac{1}{2}$ " X 30" aluminum pipe with a 3" stamped aluminum cap and the following new bearing trees:
6" White Ash N.46 E. 16.82'
8" White Ash S.04 W. 5.12'
6" Red Maple N.87 W. 24.21'
6' Steel sign rail East 2.00'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Corner recorded in Gogebic County Liber 4, Page 85 on 6/16/92.
Corner research on file with Gogebic County records.

Recovered the monument as described and the bearing trees as follows:
7" White Ash N.47 E. 16.81'
8" White Ash S.04 W. 5.13'
7" Red Maple N.87 W. 24.22'
6' Steel sign rail N.75 E. 1.94'

No evidence remains of the original bearing trees.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
New bearing tree referenced:
15" Hemlock N.04 W. 24.40'

PEER GROUP APPROVAL
Richard L. Drahn 5/13/98
COUNTY REPRESENTATIVE



Signed by Richard L. Drahn Date May 4, 1998

Surveyor's Michigan License No. 21564