

**SURVEY &
REMONUMENTATION**

SEP 08 1998

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

Register's Office } ss.
Gogebic County }

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>47</u> N R <u>44</u> W	<u>K-8</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Received for record the
23RD day of JULY
A. D. 1998 at 11:35 o'clock
A M., and recorded in
Liber 7 of CORNERS
on page 25
Ramona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter corner common to sec's 23 & 24, T47N, R44W

I, John P. Goss, in a field survey on June 30, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Corner established by William Burt, U.S. Deputy Surveyor, in 1848.
Original bearing trees: Hemlock 10" - S 58° E - 32 links (21.12')
Yellow Birch 10" - N 40° W - 21 links (13.86')
On June 15, 1972, Donald D. Lappala, RLS, USFS, restored corner position at record bearing and distance from decayed hemlock windfall and stump hole of the Yellow Birch, and natural feature ties. He set a 2½" I.D. iron pipe with a capped 3" circular bronze tablet which reads: T.47 N., R.44 W.; 1/4; S-23, S-24; R.L.S. 12585; 1971, from which he established the following reference objects: 10" Hemlock - N 30° E - 21.5'; 12" Hemlock - S 07° W - 12.4'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
6" Yellow Birch - N 87° W - 22.4'; 4"x4" Cedar sign post - S 75° E - 2.8'
He recorded said corner in U.S. Forest Service Liber P-21 on August 10, 1972.
Found the stump of the Hemlock S 58° E - 32 links.
Found Lappala monument and witnesses.
I updated the monument and accessories as noted below to state and county specification.

FEEB GROUP APPROVAL
Richard R. Drahn 7/22/98
COUNTY REPRESENTATIVE

Act 74 research on file.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
From the found monument I established the following existing and new reference objects:
14" Hemlock N 30° E 21.59'
15" Hemlock S 07° W 12.45'
11" Yellow Birch N 87° W 22.21'
11" Hemlock Due East 36.29'
4"x4" Cedar Sign post S 75° E 2.45' to face
(All measurement taken to nail in side of tree)



Signed by John P. Goss
Surveyor's Michigan License No. 23509
U.S.F.S. No. P-21

Date June 30, 1998