

SURVEY & REMONUMENTATION

SEP 08 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Gogebic

(County)

Located In:

Corner Code #

- | | | | |
|------------------------------------|---------------|---------------|------|
| 1. Public Land Survey | T <u>47</u> N | R <u>44</u> W | K-10 |
| | T | R | |
| | T | R | |
| | T | R | |
| 2. Property Controlling in Section | S | T | R |
| | S | T | R |
| 3. Miscellaneous Property in Sec. | S | T | R |
| | S | T | R |

Register's Office }
Gogebic County } ss.

Received for record the
23RD day of JULY
A. D. 1998 at 11:35 o'clock
A m., and recorded in
Liber 7 of CORNERS
on page 27
Ramona Collins, Deputy
Register of Deeds
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter Corner common to sec's. 25 & 26, T47N, R44W

I, John P. Goss, in a field survey on July 9, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:
Corner established by William Burt, U.S. Deputy Surveyor, in 1848.
Original bearing trees: Yellow Birch 12" S 65° E 18 links
Hemlock 8" N 75° W 12 links
On June 15, 1971, Donald D. Lappala, RLS, USFS, restored corner position at record bearing and distance from the two original bearing trees and natural feature ties. He set a 2 1/2" I.D. iron pipe with 3" Circular bronze tablet which reads: T.47 N., R.44 W.; 1/4; S-25, S-26; R.L.S. 12585; 1971, from which he established the following reference objects: 5" Sugar Maple - N 62° E - 6.8'; 10" White Spruce - S 60° E - 8.9'; 5" Sugar Maple - S 23° E - 12.4';

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
4"x4" Cedar post - N 65° W - 2.7'
He recorded said corner in U.S. Forest Service Liber T-21, on August 10, 1972.
Found Donald D. Lappala monument and witnesses.
I updated the monument and accessories as noted below to state and county specification.
Act 74 research on file.

PEER GROUP APPROVED
Richard L. Walsh 7/22/98
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
From found monument I established the existing and new reference objects:
7" Sugar Maple N 62° E 6.81'
14" White Spruce S 60° E 8.92'
7" Sugar Maple S 18° E 12.44'
13" Maple N 17° W 17.82'
4"x4" Cedar Post N 65° W 3.0' to face (poor shape)
6' Rail & sign S 80° W 1.82' to face
(All measurement taken to nail in side of tree)



Signed by John P. Goss
Surveyor's Michigan License No. 23509

Date July 9, 1998

U.S.F.S. No. T-21