

**SURVEY & REMONUMENTATION**

OCT 9 1996

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>47N.</u> R <u>44W.</u>	<u>K-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register's Office }  
Gogebic County } ss.

Received for record the  
10<sup>th</sup> day of JUNE  
A. D. 1996 at 10:00 o'clock  
A m., and recorded in  
Liber 5 of CORNERS  
on page 388  
Ramona Collins Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Sec. Cor. 25, 26, 35 & 36; T.47 N., R.44 W.

I, Richard L. Drahn, in a field survey on May 27, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

Corner established by William Burt in 1848. Original B.T.s --- Lynn 14" S.40 E. 35 links (23.10') --- Hemlock 12' N.40 W. 42 links (27.72') --- Corner restored by Donald D. Lappala, RLS12585 on 6/3/71 from the remains of the two original bearing trees, line trees north and south and natural features north and south. He set a 2½" iron pipe with a 3" stamped brass cap and the following new bearing trees: --- 14" (18") Sugar Maple N.06 W. (N.07 W.) 16.8' (16.70') --- 15" Hemlock (now a cut down Hemlock) S.88 E. 7.9' --- 14" (15") Sugar Maple S.65 W. (S.66 W.) 36.1' (36.27') --- 4" X 4" Cedar sign post South 2.7' (now down at S.01 W. 2.6') --- Corner recorded in Gogebic County in USFS Liber, Page V-21 on 8/10/72.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Act 74 research form on file with Gogebic County records.

Recovered the monument as described and the bearing objects as noted in parentheses above. A large stump hole with basswood sprouts remains from the original Lynn B.T.

PEER GROUP APPROVED

Richard L. Drahn 6/6/96  
COUNTY REPRESENTATIVE

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Bearing objects referenced:

- 7' Steel sign rail South 2.7'
- 10" Sugar Maple N.80 E. 32.76'



Signed by Richard L. Drahn

Date May 29, 1996

Surveyor's Michigan License No. 21564