

SURVEY & REMONUMENTATION

SEP 08 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } Es.

For corners in

Gogebic

(County)

Located In:

Corner Code #

1. Public Land Survey

T46NR44W K- 1
T47NR44W K- 13

2. Property Controlling in Section

S T R
S T R

3. Miscellaneous Property in Sec.

S T R
S T R

Received for record this
23RD day of JULY
A. D. 1998 at 11:40 o'clock
A m., and recorded in
Liber 7 of CORNERS
on page 28
Ramona Collins Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section Corner common to sec's. 1, 2, 35 & 36,
T.46-47 N, R.44 W

I, John P. Goss, in a field survey on July 10, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

DEED GROUP APPROVED
Richard H. Deahn 7/22/98
COUNTY REGISTER

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt, U.S. Deputy Surveyor, in 1847.

- Original bearing trees:
- 1. Sugar Maple 12" N 59° E 37 links
 - 2. Cedar 9" N 71° W 13 links
 - 3. Lynn 22" S 50° W 30 links
 - 4. Maple 8" S 64° E 11 links

On June 8, 1971, Donald D. Lappala, RLS, USFS, restored corner position at record bearing and distance from the remains of the four original bearing trees and natural feature ties. He set a 2 1/2" I.D. iron pipe with 3" Circular bronze tablet which read: T.46-47 N., R.44 W.; S1, S-2, S-35, S-36; R.L.S. 12585 1971.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

He established the following reference objects:

- 8" Yellow Birch - N 02° W - 31.0' (stump now) 4" Yellow Birch - S 51° E - 28.8'
 - 9" Sugar Maple - S 76° W - 12.4' (Stub); 4"x4" Cedar sign Post - East- 8.9' (down)
- In 1986, J. Exking added the following reference objects:
- 5" Yellow Birch - S 85° E - 14.54' 7" Sugar Maple - S 63° W - 15.15'

D. Lappala recorded said corner in U.S. Forest Service Liber Z-21 On Aug. 10, 1972 Found Lappala Monument and Lappala & Exking reference objects.

I updated the monument and accessories as noted below to state and county specification.

Act 74 research on file.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From found monument I established the existing and new reference objects:

- 8" Yellow Birch S 85° E 14.55'
- 8" Sugar Maple S 63° W 15.15'
- 13" Yellow Birch N 72° W 27.58'
- 6' Rail & Sign South 1.72' to face

(All measurement taken to nail in side of tree)



Signed by John P. Goss

Date July 10, 1998

Surveyor's Michigan License No. 23509

U.S.F.S. No. Z-21