

SEP 08 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogebic County } ss.

For corners in

Gogebic  
(County)

Located In:

Corner Code #

- |                                    |                           |            |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey              | T <u>47N</u> R <u>44W</u> | <u>L-3</u> |
|                                    | T _____ R _____           | _____      |
|                                    | T _____ R _____           | _____      |
|                                    | T _____ R _____           | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____   | _____      |
|                                    | S _____ T _____ R _____   | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____   | _____      |
|                                    | S _____ T _____ R _____   | _____      |

Received for record the  
14<sup>th</sup> day of MAY  
A. D. 1998 at 3:20 o'clock  
P m., and recorded in  
Liber 6 of CORNERS  
on page 378.

Ramona Collins, Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

$\frac{1}{4}$  Corner 1 & 12; T.47 N., R.44 W.

I, Richard L. Drahn in a field survey on April 28, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by William Burt in 1848. Original B.T.s --- Hemlock 12" S.53 E. 31 links (21.78') --- Fir 6" N.52 W. 12 links (7.92') --- Corner position re-established by John R. Garske (28410) by single proportionate methods on 8/24/92. He set a 2 1/2" X 30" aluminum pipe with a 3" stamped aluminum cap and the following new B.T.s:

- |     |                 |         |        |
|-----|-----------------|---------|--------|
| 7"  | Maple           | N.12 W. | 16.47' |
| 10" | Maple           | S.78 E. | 12.26' |
| 8"  | Maple           | S.68 W. | 19.77' |
| 6'  | Steel sign rail | S.26 E. | 2.77'  |

Corner recorded in Gogebic County Liber 4, Page 102 on 9/9/92.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner research on file with Gogebic County records.

Recovered the monument as described and the bearing trees as follows:

- |     |                 |         |        |
|-----|-----------------|---------|--------|
| 7"  | Sugar Maple     | N.12 W. | 16.48' |
| 10" | Sugar Maple     | S.81 E. | 12.30' |
| 8"  | Sugar Maple     | S.66 W. | 19.73' |
| 6'  | Steel sign rail | S.21 E. | 2.76'  |

No evidence remains of the original B.T.s.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:

- |    |             |         |        |
|----|-------------|---------|--------|
| 6" | Sugar Maple | S.03 E. | 19.59' |
|----|-------------|---------|--------|

PEER GROUP APPROVED  
Richard L. Drahn 5/13/98  
COUNTY REGISTER



Signed by Richard L. Drahn Date May 3, 1998

Surveyor's Michigan License No. 21564