SURVEY &
REMONUMENTATION

SEP 0 8 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's office } ss.
Gogebic County }
Received for record the 14TH day of MAY A. D. 19 98 at 3:20 o'clock P m., and recorded in Liber 6 of CORNERS on page 379
Ramona Collins Deputy
Register of Deeds

Register of Deeds Stamp & File Number

For corners in

Gogebic (County)

	Located In:	Corner Code #
1. Public Land Survey	T 47N R 44W	L-5
	T ___ R ___	
	T ___ R ___	
	T ___ R ___	
2. Property Controlling	S ___ T ___ R ___	
in Section	S ___ T ___ R ___	
3. Miscellaneous	S ___ T ___ R ___	
Property in Sec.	S ___ T ___ R ___	

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____



Quarter Corner 12 & 13; T.47 N., R.44 W.

I, Richard L. Drahn in a field survey on April 17, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by William Burt in 1848. Original B.T.s --- Sugar 20" N.25 E. 50 links (33.00') --- Elm 18" S.25 W. 10 links (6.60') --- Corner re-established by John R. Garske (28410) on 10/30/92 by single proportionate methods. He set a 2½" X 30" aluminum pipe with a 3" stamped aluminum cap and the following new B.T.s:

12"	Maple	N.81 E.	34.25'
9"	Maple	S.09 E.	17.05'
13"	Maple	N.42 W.	32.23'
6'	Steel sign rail	S.59 W.	2.38'

Corner recorded in Gogebic County Liber 4, Page 181 on 11/9/92.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner research on file with Gogebic County records.

Recovered the monument as described and the bearing trees as follows:

13"	Sugar Maple	N.18 E.	34.24'
11"	Sugar Maple	S.12 E.	17.04'
14"	Sugar Maple	N.43 W.	32.22'
6'	Steel sign rail	S.56 W.	2.36'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:

6"	Sugar Maple	S.80 E.	37.70'

PEER GROUP APPROVED
Richard L. Drahn 5/13/98
COUNTY REPRESENTATIVE

STATE OF MICHIGAN
RICHARD L. DRAHN
LAND SURVEYOR
No. 21564
REGISTERED LAND SURVEYOR

Signed by Richard L. Drahn Date April 18, 1998

Surveyor's Michigan License No. 21564

USFS J-23

379

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983