

SURVEY &  
REMONUMENTATION

SEP 08 1998

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Gogebic  
(County)

Located In:

Corner Code #

- |                                    |                           |            |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey              | T <u>47N</u> R <u>44W</u> | <u>L-7</u> |
|                                    | T _____ R _____           | _____      |
|                                    | T _____ R _____           | _____      |
|                                    | T _____ R _____           | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____   | _____      |
|                                    | S _____ T _____ R _____   | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____   | _____      |
|                                    | S _____ T _____ R _____   | _____      |

Register's Office }  
Gogebic County } ss.

Received for record the  
14<sup>TH</sup> day of MAY  
A. D. 1998 at 3:20 o'clock  
P m., and recorded in  
Liber 6 of CORNERS  
on page 380  
Ramona Collins, Dep.  
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Quarter Corner 13 & 24; T.47 N., R.44 W.

I, Richard L. Drahn in a field survey on April 21, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by William Burt in 1848. Original corner, 15" Yellow Birch. Original B.T. --- 12" Hemlock N.25 E. 25 links(16.50') --- Corner restored by Richard L. Drahn (21564) on 10/31/75 in the remains of the original Y. Birch corner tree stump and at record bearing and distance from the remains of the original Hemlock bearing tree. He set a 2" X 5' iron pipe with a 3" stamped brass cap and the following new B.T.s:

14"	Hemlock	N.81 W.	43.9'
8"	Black Ash	S.86 E.	13.8'
14"	Cedar	S.18 E.	26.4'
7'	Steel sign rail	S.25 E.	2.0'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner recorded in Gogebic County Liber 1, Page 167 on 1/27/76.

Corner research on file with Gogebic County records.

Recovered the monument as described and the bearing trees as follows:

17"	Hemlock	N.80 W.	43.83' (new nail)
11"	Black Ash	S.86 E.	13.78'
14"	Cedar	S.18 E.	26.39'
7'	Steel sign rail	S.26 E.	1.92'

No evidence remains of the original corner tree. A stump hole with fragments of Hemlock wood and bark still remains from the original B.T.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree established:

9"	Hemlock	N.09 W.	43.95'
----	---------	---------	--------

PEER GROUP APPROVED  
Richard L. Drahn 5/13/98  
COUNTY REPRESENTATIVE



Signed by Richard L. Drahn Date April 22, 1998

Surveyor's Michigan License No. 21564