

SURVEY & REMONUMENTATION

SEP 08 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

For corners in

Gogebic
(County)

Located In:

Corner Code #

- | | | | |
|------------------------------------|---------------|---------------|------|
| 1. Public Land Survey | T <u>47</u> N | R <u>44</u> W | L-11 |
| | T | R | |
| | T | R | |
| | T | R | |
| 2. Property Controlling in Section | S | T | R |
| | S | T | R |
| 3. Miscellaneous Property in Sec. | S | T | R |
| | S | T | R |

Received for record the
23RD day of JULY
A. D. 1998 at 11:40 o'clock
A m., and recorded in
Liber 7 of CORNERS
on page 29
Ramona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter corner common to sec's 25 & 36, T47N, R.44W

I, John P. Goss, in a field survey on July 13 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

DEED GROUP APPROVAL
Richard L. Deah 7/22/98
COUNTY REGISTER

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by William Burt, U.S. Deputy Surveyor, in 1848.

Original bearing trees: Yellow Birch 20" N 45° E 12 links
Yellow Birch 16" S 45° W 20 links

On June 3, 1971, Donald D. Lappala, RLS, USFS, restored corner position at record bearing and distance from the two original bearing trees and natural feature ties. He set a 2 1/2" I.D. iron pipe with 3" circular tablet which reads: T.47 N., R.44 W.; 1/4; S-25, S-36; R.L.S. 12585; 1971. He established the following reference objects: 9" Sugar Maple - N 56° W - 13.4'; 14" Sugar Maple N 12° E - 25.1'; 12" Sugar Maple - S 48° E - 26.8'; 4"x4" Cedar sign post -

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: South - 2.8'

He recorded said corner in U.S.F.S. Liber V-23 on August 10, 1972.
Found Donald D. Lappala monument and witnesses.
Found at record bearing and distance from the two original bearing trees.
The first is now a yellow birch stump at ground level and the second is now a decayed yellow birch stump.

I updated the monument and accessories as noted below to state and county specification.

Act 74 research on file.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the found corner monument I established the following existing and new reference objects:

- | | | |
|-----------------|---------|--------|
| 16" Sugar Maple | N 56° W | 13.49' |
| 19" Sugar Maple | N 12° E | 25.10' |
| 16" Sugar Maple | S 48° E | 26.80' |
| 9" Sugar Maple | S 77° W | 10.99' |

4"x4" Cedar sign post South 2.6' to face
(All measurement are taken to nail in side of tree)



Signed by John P. Goss

Date July 13, 1998

Surveyor's Michigan License No. 23509

U.S.F.S. No. V-23