

**SURVEY &
REMONUMENTATION**

SEP 08 1998

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

Register's Office }
Gogebic County } ss.

For corners in SECTION
Gogebic
(County)

Located In: Corner Code #

- | | | | |
|------------------------------------|---------|-----------------|-------|
| 1. Public Land Survey | | T 47N R 44W | M-4 |
| | | T _____ R _____ | _____ |
| | | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ | T _____ R _____ | _____ |
| | S _____ | T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ | T _____ R _____ | _____ |
| | S _____ | T _____ R _____ | _____ |

Received for record the
14TH day of MAY
A. D. 1998 at 3:30 o'clock
P m., and recorded in
Liber 6 of CORNERS
on page 384
Ramona Collins Dep.
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quater Corner 12 & 7; T.47 N., R.43-44 W.

I, Richard L. Drahn in a field survey on April 17, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 8/10/1847. Original B.T.s --- Hemlock 16" S.67 W. 13 links (8.58') --- Sugar 7" S.81 E. 37 links (24.42') --- Corner restored by Richard L. Drahn on 10/31/75 from the remains of the two original B.T.s and from an original line tree 6.71 chains south. He set a 2" X 60" iron pipe with a 3" stamped brass cap and the following new B.T.s:

12"	Cedar	N.12 E.	39.8'
10"	Yellow Birch	S.55 E.	25.1'
14"	Yellow Birch	S.57 W.	55.7'
7'	Steel sign post	N.87 W.	2.1'

Corner recorded in Gogebic County Liber 1, Page 163, on 1/27/76.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner research on file with Gogebic County records.

Recovered the monument as described and the bearing trees as follows:

12"	Cedar	N.12 E.	39.74'	(new nail)
13"	Yellow Birch	S.56 E.	25.19'	" "
15"	Dead Yellow Birch	S.58 W.	54.47'	" "
7'	Steel sign rail	N.88 W.	2.10'	

The original B.T.s are now both badly decayed stumps. The blazed Y. Birch line tree recovered in 1975 is now a Yellow Birch stump, decayed to ground line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing trees referenced:

5"	Sugar Maple	S.66 W.	42.44'
10"	Sugar Maple	N.57 W.	29.16'

PEER GROUP APPROVED

Richard L. Drahn 5/13/98
COUNTY REGISTER



Signed by Richard L. Drahn Date April 18, 1998

Surveyor's Michigan License No. 21564