

SURVEY & REMONUMENTATION

SEP 08 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Gogebic
(County)

Located In: Corner Code #

- 1. Public Land Survey T 47N R 44W M-5
- 2. Property Controlling in Section T _____ R _____
- 3. Miscellaneous Property in Sec. T 47N R 43W A-5

Register's Office }
Gogebic County } ss.

Received for record the
14th day of MAY
A. D. 1998 at 3:30 o'clock
P m., and recorded in
Liber 6 of CORNER
on page 385
Ramona Collins Dep.
Register of Deeds

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Section Corner 12, 13, 7 & 18; T.47 N., R.43-44 W.

I, Richard L. Drahn in a field survey on April 17, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 8/10/1847. Original B.T.s --- Cedar 10" s.66 W. 34 links (22.44') --- Fir 10" N.51 E. 29 links (19.14') --- Hemlock 6" S.50 E. 40 links (26.40') ---
R. Drahn & F. Hintsala recovered the Hemlock and Cedar still scribed on 10/17/67. Corner monumented by Richard L. Drahn (21564) on 05/28/75 from the remains of the Cedar and Hemlock B.T.s (Cedar still scribed). He set a 2 1/2" X 60" iron pipe with a 3" stamped brass cap and the following new B.T.s:

- 8" Hemlock S.14 W. 21.5'
- 6" Sugar Maple S.33 E. 9.2'
- 7" Sugar Maple S.11 W. 16.8'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 7' Steel sign rail West 2.1'

Corner recorded in Gogebic County, Liber 1, Page 165 on 1/23/76.

Corner research on file with Gogebic County records.

Recovered the monument as described and the bearing trees as follows:

- 10" Hemlock N.14 W. 21.55' (new nail)
- 8" Sugar Maple S.33 E. 9.24' " "
- 8" Sugar Maple S.10 W. 16.93' " "

Portions of a decayed, downed Cedar and a decayed Hemlock stump still remains from the original bearing trees.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:

- 4" Sugar Maple S.87 W. 16.22'

PEER GROUP APPROVED
Richard L. Drahn 5/13/98
COUNTY REGISTER



Signed by Richard L. Drahn Date April 18, 1998

Surveyor's Michigan License No. 21564