

SURVEY & REMONUMENTATION

SEP 08 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Gogebic
(County)

Located In: Corner Code #

- | | | | |
|------------------------------------|---|--|----------------|
| 1. Public Land Survey | | T <u>47</u> N R <u>44</u> W | M-6 |
| | | T 47 N R 44 W | M-6 |
| | | T <u>47</u> N R <u>43</u> W | A-6 |
| 2. Property Controlling in Section | S | T | R |
| 3. Miscellaneous Property in Sec. | S | T | R |

Register's Office }
Gogebic County } ss.

Received for record the
14th day of MAY
A. D. 1998 at 3:30 o'clock
P m., and recorded in
Liber 6 of CORNER
page 386
Ramona Collins Dep.
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter Corner 13 & 18; T.47 N., R.43-44 W.

I, Richard L. Drahn a field surveyor on April 17, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5			4		3			2		1	
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 8/10/1847. Original B.T.s --- Y. Birch 12" N.31 W. 11 links (7.26') --- Hemlock 14" S.24 E. 57 links (37.62') --- Corner restored by Richard L. Drahn (21564) on 5/28/75 from the remains of the two original bearing trees and from natural features north and south. He set a 2" X 60" iron pipe with a 3" stamped brass cap and the following:

6" White Ash	N.30 E.	30.0'
7" Sugar Maple	S.70 E.	32.2'
5" Sugar Maple	S.01 E.	10.3'
7' Steel sign rail	S.49 W.	2.4'

Corner recorded in Gogebic County Liber 1, Page 166 on 1/27/76.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner research on file with Gogebic County records.

Recovered the monument as described and the bearing trees as follows:

8" White Ash	N.27 E.	29.89'	(new nail)
7" Sugar Maple	S.73 E.	32.19'	(dead stub)
6" Sugar Maple	S.02 E.		(dead and down)
7' Steel sign rail	S.36 W.	2.82'	(reset)

All that remains of the original B.T.s is a depression for the Y. Birch and a stump hole for the Hemlock.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing trees referenced:

6" Sugar Maple	S.36 W.	40.89'
8" White Ash	S.02 E.	34.53'

PEER GROUP APPROVED

Richard L. Drahn 5/13/98
COUNTY REGISTER



Signed by Richard L. Drahn

Date April 18, 1998

Surveyor's Michigan License No. 21564