

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

Register's Office }  
 Gogebic County } ss.

For corners in

Gogebic  
 (County)

Located In:

Corner Code #

Received for record the  
21<sup>st</sup> day of JULY  
 A. D. 1995 at 1:40 o'clock  
P m., and recorded in  
 Liber 5 of CORNERS  
 on page 273  
*Ramona Collins, Deputy*  
 Register of Deeds

1. Public Land Survey Sec. 13 T47N R 46W M - 6  
 T R  
47N R 45W A - 6  
 T R  
 2. Property Controlling S T R  
 in Section S T R  
 3. Miscellaneous S T R  
 Property in Sec. S T R

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

1/4 cor. comm. to sec's. 13 and 18

I, John P. Goss, in a field survey on May 27, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by John Burt on Sept. 7, 1847. Set post.  
 Original bearing trees: Sugar 12" S 24° E 35 links  
 Sugar 20" S 83° W 20 links

John P. Goss in 1983 using Plymouth Mining Company map of 1920 reestablished this corner and recorded it in Liber 2 on Page 312 of Land Corners for Gogebic County. Established the following witnesses and distances: T.Pole N 41° W-39.51'; 5" Maple- N 43° E- 51.87'; centerline top nut fireHyd- S 24° W-25.08'; (2) concrete Monument - North- 58.26' & 189.41' from corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found (3) of the witnesses objects from John P. Goss certification. I updated the corner monument and accessories as noted below to state and county specification.

Act 74 reseach on file with the County Register of Deeds Office.

PEER GROUP APPROVED

*Richard P. ...*  
 COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set a 2½" brass cap with a 2" stem at 1" below asphalt road surface. Cap is Stamed T47N, R45-46W; S-13, S-18, 1995; P.S. 23509. I established the following bearing trees and reference objects.

T.Pole N 41° W 39.51'  
 10" Maple N 48° E 51.87'  
 E top nut Fire Hyd. S 24° W 25.08'  
 Reference Monument consisting of 2½"x30" aluminum monument with a 3½" aluminum cap Stamped to indicate the corner position. S 39° E- 39.79' with a 6' steel rail and sign 1.08'.



Signed by John P. Goss

Date May 28, 1995

Surveyor's Michigan License No. P.S. 23509

Fed. No. L-25