

DEC 15 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Gogebic
(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|-------------------------|-------|
| 1. Public Land Survey | T 46N R 45W | B-1 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T 47N R 45W | B-13 |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1/4 Corner 6 & 31; T.46-47 N., R.45 W

Richard L. Drahn in a field survey on November 2, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 8/31/1847. Original B.T.s --- Y. Birch 20" N.23 E. 20 links (13.20') --- 12" Sugar N.65 W. 34 links (22.44') ---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original corner position found marked by a 4" X 4' downed Cedar post at record bearing and distance from the stump remains of the two original B.T.s. The first is a 24-30" badly decayed Y. Birch stump. The second one is now a 16-20" Sugar Maple stump, decayed to well below ground line. The 1.75 chain distance west to "stream 3 lks., SE" and the 4.00 chain distance west to "ascend ledge/knob of synite, 15'" check to within 3 feet.

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner I set a 2 1/2" X 30" Aluminum pipe with a 3 1/4" aluminum cap, stamped to indicate the corner position and the following new B.T.s:

- | | | | |
|-----|-----------------|---------|--------|
| 5" | Red Maple | N.80 W. | 29.62' |
| 5" | Sugar Maple | N.14 E. | 19.65' |
| 11" | Red Maple | S.18 E. | 7.87' |
| 6' | Steel sign rail | S.83 E. | 2.42' |

Register's Office } ss.
Gogebic County }

Received for record the
25th day of NOVEMBER
A. D. 1998 at 10:00 o'clock
A m., and recorded in
Liber 7 of CORNELLS
on page 88.
Ramma Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

FREE GROUP APPROVAL
Richard L. Drahn 11/24/98
COUNTY _____



Signed by Richard L. Drahn Date November 9, 1998

Surveyor's Michigan License No. 21564