

SURVEY & REMONUMENTATION

1993

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**

Gogebic
 (County)

Located In:

Corner Code ##

- 1. Public Land Survey Section 8 T 47N R 45W C-4
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

- 4. Lot No. _____, Recorded Plat _____
 - 5. Private Claims _____
- One-quarter corner common to S-7 & S-8, T47N, R45W**

I, John R. Garske, in a field survey on November 30, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Survey by William Burt, 1848. Set sugar post from which a 7" fir bears S40°E, 15 links and a 10" fir bears N50°W, 16 links. No original evidence found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found a "T" iron with 1" cap. Set by G. Wilson, R.L.S. in plat work for Indianhead Mountain in early 1970's. The corner was used in the subdivision of Section 8 and has been used and accepted by county agencies, local residents and in various surveys.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced found "T" iron with 2 1/2" x 30" aluminum county monument - with 3" aluminum cap stamped: County Remonumentation; T47N, R45W; 1/4 cor.; S-7; S-8; 1993; R.L.S. 28410. Established the following bearing trees and reference objects:

- 10" sugar - S77°W - 13.69 feet
- 3" Ironwood - N30°E - 6.10 feet
- 8" Ironwood - S22°E - 12.64 feet
- Steel sign post - due east - 2.00 feet

Register's Office } ss.
 Gogebic County }

Received for record the 16th day of DECEMBER A. D. 1993 at 2:25 o'clock P m., and recorded in Liber 4 of CORNERS on page 299.
Betty L. Saari Deputy Register of Deeds

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Signed by John R. Garske
 Surveyor's Michigan License No. 28410

Date 12/9/93

