

SURVEY &  
REMONUMENTATION

1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Gogebic  
(County)

Located In:

Corner Code #/

1. Public Land Survey Section 8 T 47N R 45W C-5  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_
2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_
3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

Section corner common to S-7, 8, 17 & 18, T47N, R45W

November 30 93

I, John R. Garske, in a field survey on \_\_\_\_\_, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Survey by William Burt, U.S.D.S., 1848. Set hemlock post from which a 12" Y. birch bears S20°E, 9 links and a 20" Y. hemlock bears N60°W, 50 links. No original evidence found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found a 1" iron pipe in a 4" diameter concrete filled pipe at the corner position. This corner has been used and documented by the Michigan Department of Transportation and other surveyors for over 25 years. It is shown on the 1969 M.D.O.T. R/W plans as surveyed by J. Smallwood, RLS.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found 4" pipe with a 1" pipe in concrete 6" below surface. Set a 3/4" x 30" rebar with a 3 1/2" stamped aluminum cap inside the 1" pipe. Established the following bearing trees and reference objects:

- Center line of Highway - due north - 43.92 feet
- S.W. corner bolt in concrete base of cross (sign) - S68°E - 92.85 feet
- 8" twin maple - S10°E - 43.72 feet
- 6" twin maple - S82°W - 45.08 feet
- Steel sign post - due north - 1.61 feet

Register's Office }  
Gogebic County } ss.

Received for record the  
16<sup>th</sup> day of DECEMBER  
A. D. 1993 at 2:30 o'clock  
P m., and recorded in  
Liber 4 of CORNERS  
on page 311.  
Betty Lassi, Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Signed by John R. Garske  
Surveyor's Michigan License No. 28410

Date 12/27/93

