

SURVEY &
REMONUMENTATION

1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Gogebic
(County)

Located In:

Corner Code #1

- | | | |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey Section 8 | T <u>47N</u> R <u>45W</u> | <u>D-5</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

One-quarter corner common to S-8 & S-17, T47N, R45W

I, John R. Garske, in a field survey on November 30, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Survey by William Burt, D.S., in 1848. Set ironwood post from which a 12" sugar bears S65°E, 56 links and a 12" Y. birch bears N65°W, 22 links. No original evidence found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found iron rod in monument box in the east bound lane of U.S. Highway No. 2. Corner used in several surveys and by the Michigan Department of Transportation for 25+ years. The corner position is referenced on 1969 M.D.O.T. R/W plans from the 1969 survey by J. Smallwood, RLS.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Iron rod in monument box - Established the following reference objects:

Set two reference monuments being standard 2 1/2" x 30" Bernsten aluminum pipes with a 3 1/2" aluminum cap stamped: County Remonumentation; T47N, R45W; R.M.; S-8; S-17; 1/4 cor.; 1993; RLS 28410; stamped with respective distances. Reference monument Number 1) due south - 42.45 feet, steel sign post - 1.38 feet. Reference monument Number 2) due north - 91.55 feet, steel sign post - 0.91 feet Reference monuments were set on line with the corner.

Register's Office }
Gogebic County } ss.

Received for record the
16TH day of DECEMBER
A. D. 1993 at 2:30 o'clock
P m., and recorded in
Liber 4 of CORNERS
on page 312
Betty Saari Deputy
Register of Deeds

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Signed by John R Garske
Surveyor's Michigan License No. 28410

Date 12-27-93

