

FEB 18 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Gogebic
(County)

Located In: Corner Code: #

- 1. Public Land Survey Section 4 T 47N R 45W E-1
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Section corner common to S-32, 33, 4, 5, T48-47N, R45W.

December 2 1993

I, John R. Garske, in a field survey on _____, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by Austin Burt, U.S.D.S., on September 4, 1847. Set B. ash post which a 10" elm bears N70°E, 31 links and a 16" hemlock bears N18°W, 29 links.

No original evidence found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I reestablished the corner at the center line intersection of a southerly and westerly trail with a northerly fence line. The fence line running north is 40 to 50 years old. This corner position is consistent with natural feature ties and was established after a diligent search failed to find any original or subsequent evidence of the corner position. Measurements to known corner positions east and south were used to verify this position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" x 30" long rebar with a standard Bernsten 3 1/2" aluminum cap 4"± below the surface stamped: County Remonumentation; T48N, R45W; S-32; S-33; S-4; S-5; T47N; 1993; RLS 28410. Established the following bearing trees and reference objects:

- 6" cherry - N87°E - 29.58 feet
- 9" balsam - S37°E - 53.70 feet
- 4" white birch - S34°W - 34.07 feet
- 16" poplar - N37°W - 28.28 feet
- A 2 1/2" diameter x 30" long aluminum pipe reference monument with a 3 1/2" diameter stamped aluminum cap w/steel sign post - north - 22.77 feet - Steel sign post - 1.92 feet

Register's Office }
Gogebic County } 68.

Received for record the
30TH day of December
A. D. 1993 at 12:20 o'clock
P m., and recorded in
Liber 4 of CORNERS
on page 316
Betty Lissie Deputy
Register of Deeds
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													



Signed by John R Garske Date 12/22/93
Surveyor's Michigan License No. 28410