

SURVEY & REMONUMENTATION

SEP 29 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the
16th day of SEPTEMBER
A. D. 1994 at 3:20 o'clock
P m., and recorded in
Liber 5 of CORNERS
on page 76
Ramona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

For corners in

Gogebic
(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey | T <u>47N</u> R <u>45W</u> | <u>E-5</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section corner common to Sections 8, 9, 16 & 17

I, John R. Garske, in a field survey on Sept. 6, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- Survey by William Burt in 1848, set alder post from which a 10" B. ash bears S60°E, 22 links.
- On May 22, 1979, E. Muller, RLS 15408 and J. Goss, RLS 23509, found a 1" iron rod in concrete using corner ties provided by the Michigan Department of State Highways and the City of Wakefield Engineer's Office. Accessories: P. pole - N43°W, 77.64 feet; N.W. cor. of Bld. found - N43°E, 40.82 feet; S.W. cor. of Bld. found - S30°E, 59.92 feet; P. pole - S15°W, 41.49 feet, recorded in Liber 1 of land corners, page 488.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found a 1" iron rod in concrete approximately 20" below the groundmarking the corner position which checks with Muller/Goss certificate as noted above. I updated the corner monument and accessories as noted below to bring them up to state and county specifications.

Record research on file with County Register of Deeds Office.

PEER GROUP

Approved

Richard L. Deahn 9/14/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A 19" long x 2 1/2" diameter aluminum pipe with a 3 1/4" aluminum cap stamped to indicate corner position was set on top of found 1" iron rod. I established the following reference objects: N.W. cor. of Bld. foundation - N51°E, 40.82 feet; S.W. cor. of Bld. foundation - S31°E, 59.92 feet; P. pole - N35°W, 28.22 feet; P. pole - S09°W, 41.49 feet.

Signed by John R. Garske
Surveyor's Michigan License No. 28410

Date 9/6/94

