

**SURVEY &
REMONUMENTATION**

AUG 08 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T47NR 45W	E-6
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register's Office }
Gogebic County } ss.

Received for record the
13th day of MAY
A. D. 1997 at 2:05 o'clock
P m., and recorded in
Liber 6 of CORNERS
on page 115
Ramona Collins Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1/4 cor. comm. to sec's. 16 & 17

I, John P. Goss, in a field survey on April 30 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by William Burt in 1848. Set tamarack post.

Original bearing trees: Tamarack 8" N 40° W 6 links

Tamarack 8" S 60° E 25 links.

John R. Garske set a 5/8 inch rebar by single proportionate measurement, on line and 1/2 the distance between the N.W. corner and the S.W. corner of Section 16. On April 26, 1982. He recorded said corner in Liber 2 on page 264 of Land

Corners for Gogebic County. He established the follows reference objects:

Power Pole N 11° W 80.05' Power Pole N 25° E 74.72'

Power Pole S 40° W 39.08'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence found, due to corner falls in centerline of road.

I found two (2) of John R. Garske witnesses from which I reestablished the corner to State and county specification.

Act 74 research on file.

PEER GROUP APPROVED

Richard P. Drahn 5/12/97
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner location I set a 5/8 inch by 20 inch rebar with a 3/4 inch aluminum cap stamped to read: County Remonumentation, T.47 N., R.45 W., 1/4; S-16, S-17, 1997; P.S. 23509. Buried 6 inches below gravel surface. I established the following reference objects:

P.Pole N 11° W 80.05'

P.Pole #41 S 40° W 39.08'

P.Pole #453 N 23° E 76.57'

Reference Monument consisting of 2 1/2" by 30"

Aluminum monument with a 3/4" aluminum cap

stamped to indicated corner position.

S 40° E - 48.57'; with 6" rail & Sign @ 1.42'

Signed by John P. Goss

Date April 30, 1997

Surveyor's Michigan License No. 23509

Fed. No. L-9

