

FEB 18 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Gogebic
(County)

Located In:

Corner Code *##*

- 1. Public Land Survey SECTION 4 T 47N R 45W G-2
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____
One-quarter corner S-4 & S-3.

December 2 19 93

I, _____, in a field survey on _____, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by William Burt on December 14, 1848. Set alder post at 38.90 chs (north to south). Bearing trees:

- 12" elm - S85°E - 77 links
- 12" spruce - S30°W - 106 links

No evidence found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found a 1/2" iron rod in broken concrete as noted in 1940's era, notes found in City of Wakefield Engineer's office. I accepted the monument found as being in the one-quarter corner location. No original evidence of the corner location exists.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found a 1/2" rebar in broken concrete and set standard Bernsten 3 1/2" aluminum cap stamped: County Remonumentation; T47N, R45W; 1/4 cor.; S-4; S-3; 1993; RLS 28410. Established the following bearing trees and reference objects:

- 8" ash - N60°E - 60.63 feet
- Power Pole #19 - S87°E - 86.07 feet
- N. post of arrow sign - N42°W - 25.40 feet
- Reference monument with 3 1/2" stamped aluminum cap with steel sign post - west - 16.70 feet, 1.17 feet to steel sign post.
- Reference monument with 3 1/2" stamped aluminum cap with steel sign post - S64°E - 44.65 feet - Steel sign post - N84°E - 0.89 feet

Signed by John R. Garske Date 12/23/93
Surveyor's Michigan License No. 28410

Register's Office } ss.
Gogebic County }

Received for record the
30TH day of DECEMBER
A. D. 1993 at 12:20 o'clock
P m., and recorded in
Liber 4 of CORNERS
on page 320
Betty Isaac Deputy
Register of Deeds

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													