

SURVEY & REMONUMENTATION

AUG 08 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>47</u> N R <u>45</u> W	<u>G-4</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Received for record the
13th day of MAY
A. D. 1997 at 2:05 o'clock
P m., and recorded in
Liber 6 of CORNERS
on page 116
Ramona Collins Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1/4 cor. comm. to sec's 9 & 10

I, John P. GOSS, in a field survey on May 2, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by William Burt in 1848. Corner is 10" Lynn
Original bearing trees: Sugar 8" S 30° W 31 links
Ironwood 10" N 25° E 45 links

Ewart C. Muller, RLS., found 3/4" iron rod and recorded said corner in Liber 1 page 306 of Land Corners for Gogebic County. In July, 1976. In 1991 John R. Garske using M-28 plans of M-28 found 3/4 inch axel rod and recorded said corner in Liber 4 page 47 of Land Corners for Gogebic County. He established the following reference objects: 4" Aspen - N 77° W - 27.08'; 8" Aspen - N 13° E - 20.76'; 4" R. Pine - S 57° W - 32.48'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence found.
Found 3/4 inch axel rod drove inside a 1 1/4 inch I.D. pipe and it checked with Garske witnesses. I updated the accessories as noted below to state and county specification.

Act 74 research on file.

BEER GROUP APPROVAL

Richard L. Dean 5/12/97
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I set a 3 1/4" diameter aluminum cap stamped: County Remonumentation; T.47 N., R.45 W.; 1/4; S-9, S-10; 1997; P.S. 23509. I established the following reference objects.

D.H. Nail in 6" Aspen	N 77° W	27.11'
D.H. Nail in 8" Aspen	N 13° E	20.78'
D.H. Nail in 7" R. Pine	S 57° W	32.60'
6' Rail & sign	Due E	2.1'



Signed by John P. Goss
Surveyor's Michigan License No. 23509

Date May 2, 1997

Fed. No. G-13