

SURVEY & REMONUMENTATION

AUG 08 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office
Gogebic County

Received for record the
13th day of MAY
A. D. 1997 at 2:05 o'clock
P M., and recorded in
Liber 6 of CORNERS
on page 117
Ramona Collins, Deputy
Register of Deeds

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T47NR 45W</u>	<u>G-5</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Sec. cor. comm. to sec's 9,10,15 & 16

I, John P. Goss, in a field survey on May 1, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by William Burt in 1848. Set Cedar Post.
Original bearing trees: Cedar 8" S 40° W 21 links
Cedar 10" N 15° E 9 links.

Ewart C. Muller, RLS. set corner from MDSH witnesses on July 28, 1976 and recorded said corner in Liber 1 page 305 of Land Corners for Gogebic County. John R. Garske set corner from MDSH witnesses in 1991 and recorded said corner in Liber 4 page 49 of Land corners for Gogebic County. Garske set a P.K. Nail and established the following witnesses. D.H Nail, in P.Pole- N 45° W- 28.54'; D.H.Nail in P.Pole- N 35° E- 50.99'; 1" iron pipe- Due East- 30.48'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence found, due to road construction.
I found a P.K. Nail and it check with Muller and Garske witnesses to (2) Power poles. I updated the accessories as noted below to state and county specification
Act 74 research on file.

PEER GROUP APPROVED
Richard P. Deane 5/12/97
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the P.K. Nail I established the following reference objects.
Nail & MSHD Tag in P.Pole #41 N 45° W 28.54'
Nail & MSHD Tag in P.Pole #487 N 35° E 50.99'
I set (2) reference monuments consisting of 2½" by 30" aluminum pipe with ¾" Aluminum cap stamped to indicate corner position.
R.M. S 56° W 48.68' & 6' rail & sign 1.1'
R.M. S 16° E 62.14' & 6' rail & sign 1.0'



Signed by John P. Goss
Surveyor's Michigan License No. 23509

Date May 1, 1997

Fed. No. J-13