

**SURVEY &  
REMONUMENTATION**

AUG 08 1997

**COMMISSION LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogebic County } ss.

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T47NR 45W	G-6
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Received for record the  
13<sup>TH</sup> day of MAY  
A. D. 1997 at 2:05 o'clock  
P m., and recorded in  
Liber 6 of CORNERS  
on page 118  
Ramona Collins, Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

1/4 cor. comm. to sec's. 15 & 16

I, John P. Goss, in a field survey on April 22 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by William Burt in 1848. Set Hemlock post.  
Original bearing trees: Sugar 12" N 20° E 14 links  
Sugar 10" S 50° W 14 links

John P. Goss, RLS, on Oct. 27, 1982 found 3/4 inch rebar in centerline of Bedell Ave. using MDOT & City of Wakefield Engineering office ties. He recorded said corner in Liber 2 on pages 310 & 311 of Land Corners for Gogebic County. He established the following reference objects: D.H. Nail in P.Pole-S 84° E- 36.35'; D.H. Nail in P.Pole-S 79° W- 30.04'; D.H. Nail in P.Pole- N 16° W- 96.82'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence could be found due to road construction.  
Found 3/4 inch rebar and it checked with my witnesses above. I updated the accessories as noted below to state and county specification.

Act 74 research on file.

PEER GROUP APPROVED  
Richard L. Decker 5/12/97  
COUNTY REGISTER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I drove the 3/4 inch rebar down and over it 1 inch below surface I place a 2 1/2" brass cap with a 2" stem, stamped T.47 N, R.45 W.; 1/4; S-15, S-16; 1997; P.S. 23509. I established the following references objects.

D.H. Nail in P.Pole #499 S 84° E 36.39'  
D.H. Nail in P.Pole #91 S 79° W 30.08'  
D.H. Nail in P.Pole #26 N 16° W 96.82'

Reference Monument consisting of 2 1/2" by 30" Aluminum monument with a 3 1/4" aluminum cap, stamped to indicated corner position.

N 42° W- 50.30'; with a 6' rail & sign @ 1.1'.

Signed by John P. Goss  
Surveyor's Michigan License No. 23509

Date April 23, 1997.



Fed. No. L-13