

**SURVEY & REMONUMENTATION**

AUG 08 1997

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogebic County } ss.

For corners in

Gogebic  
(County)

Located In:

Corner Code #

- |                                    |                            |            |
|------------------------------------|----------------------------|------------|
| 1. Public Land Survey              | T <u>47</u> NR <u>45</u> W | <u>H-5</u> |
|                                    | T ___ R ___                | _____      |
|                                    | T ___ R ___                | _____      |
|                                    | T ___ R ___                | _____      |
| 2. Property Controlling in Section | S ___ T ___ R ___          | _____      |
|                                    | S ___ T ___ R ___          | _____      |
| 3. Miscellaneous Property in Sec.  | S ___ T ___ R ___          | _____      |
|                                    | S ___ T ___ R ___          | _____      |

Received for record the  
13<sup>th</sup> day of MAY  
A. D. 1997, at 2:05 o'clock  
P m., and recorded in  
Liber 6 of CORNERS  
on page 120  
Ramona Collins, Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

1/4 cor. comm. to sec's 10 & 15

I, John P. GOSS, in a field survey on May 8, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5							●					
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by William Burt in 1848. Set Ironwood post.  
Original bearing trees: Y. Birch 5" N 55° W 15 links  
Sugar 10" S 35° E 20 links

In September of 1991 John Garske found a 1 1/4" iron rod, being the Northwest corner of Plat of Halberg, accessed as corner and record it in Liber 4 page 48 of Land Corners for Gogebic County. From the 1 1/4" iron rod he established the following reference objects: 8" Aspen - Due North - 47.77'; P.Pole #28 - N 87° E - 19.55'; N.W. corner of rock foundation of house #400 - S 33° E - 91.00'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence could be found due to road construction.  
I found the 1 1/4" iron rod and it checked with Garske witnesses. I updated the accessories as noted below to state and county specification.

Act 74 research on file.

PEER GROUP APPROVED  
Richard P. Draker 5/12/97  
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replaced the 1 1/4" iron rod with a 2 1/2" by 30" aluminum pipe with a 3 1/4" aluminum cap stamped as follows: County Remonumentation; T 47 N, R 45 W; 1/4; S-10, S-15 1997; P S 23509. I established the following reference objects:

8" Aspen (stump)	Due North	44.77'
P.Pole 7/10	N 87° E	19.55'
P.Pole #28	S 70° E	23.72'
9" Aspen	N 15° W	60.00'
6" Ash	S 57° W	58.89'
6' Rail & Sign	N 59° E	12.8'

(All measurement taken to nail in side of tree or P.Pole)

Signed by John P. Goss  
Surveyor's Michigan License No. 23509

Date May 8, 1997



Fed. No. J- 15