

DEC 15 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office } Gogebic County } ss.

Received for record the 25TH day of NOVEMBER

A. D. 19 98 at 10:00 o'clock

A m., and recorded in Liber 7 of CORNERS

on page 89

Romona Collins Deputy Register of Deeds

Register of Deeds Stamp & File Number

For corners in

Gogebic (County)

Located In:

Corner Code #

1. Public Land Survey	T 46N R 45W	H-1
	T R	
	T R	
	T 47N R 45W	H-13
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

4. Lot No. , Recorded Plat
5. Private Claims

1/4 Corner 3 & 34; T.46-47 N., R.45 W.

Richard L. Drahn in a field survey on October 27, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 8/30/1847. Original corner --- 5" Cedar --- Original B.T. --- Spruce 14" N.02 W. 18 links (11.88') ---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Restored corner position in the root remains of the original corner tree. It is now a downed, badly decayed 10-14" Cedar. The original B.T. is now a large windthrown stump hole. The 11.00 chain distance East to "enter swamp, N-S" checks to within 1'. The 13.40 chain distance East to "descend ledge 40', perpendicular" checks to within 7'.

3/4" iron pipe with a 2" X 2" X 48" Cedar guard stake bears N.61 W., 6.50' from the original corner position.

Corner research on file with Gogebic County records.

PEER GROUP APPROVED
Richard L. Drahn 11/24/98
COUNTY REGISTER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 3/4" X 4' solid aluminum rod with a 3/4" aluminum cap, stamped to indicate the corner and the following B.T.S.:

10"	Cedar	N.80 W.	29.89'
9"	Cedar	S.15 E.	34.21'
8"	Cedar	N.64 E.	25.28'
6'	Steel sign rail	S.40 E.	2.36'



Signed by Richard L. Drahn Date November 9, 1998

Surveyor's Michigan License No. 21564