

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
 Gogebic County } ss.

For corners in
Gogebic
 (County)

Located in: _____ Corner Code # _____

1. Public Land Survey T47NR45W K-5
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Section Corner common to Sections 11, 12, 13, and 14.

Received for record the
2ND day of JUNE
 A. D. 2000 at 10:20 o'clock
A. m., and recorded in
 Liber 7 of CORNERS

on page 363
Cheryl Rippe, Reg.
 Register of Deeds

Register of Deeds Stamp & File
 Number

**SURVEY &
 MONUMENTATION**
JAN 05 2001
SECTION

I, John R. Garske, in a field survey on March 30, 2000, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and / or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3			1
3													
4	7						8			9			10
5													11
6	18			17			16			15			14
7													
8	19			20			21			22			23
9													
10	30			29			28			27			26
11													
12	31			32			33			34			35
13													36

A. Description of original monument and accessories and / or subsequent restoration:

Original survey by William Burt in 1848.
 Original Corner: Tamarack post
 Original Bearing Trees: 14" Spruce N 60° W 95 Links
 12" Tamarack S 50° E 14 Links

B. Description of corner evidence found and / or method applied in restoring or re-establishing corner:

I found an old bearing tree with tag placed by Keweenaw Land Company, also an old fence running East and West. I established the section corner at the intersection of the ancient E-W fence line and the centerline of Morgan Road. This location is in harmony with local property lines and checks with known corners west and south.

Record research on file.

DEED GROUP ACKNOWLEDGMENT
Richard D. Neal 5/24/00
 COUNTY REGISTER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I set a 3/4" aluminum cap at the intersection of the centerline of Morgan Road and fenceline, from which I established the following witnesses:

6" Aspen with Keweenaw tag	N 65° E	48 Feet ±
6" Balsam	S 23° E	88.02 Feet
3" Balsam	N 49° E	125.75 Feet
Reference Monument	N 69° W	45.00 Feet
(3/4" aluminum cap set on a 5/8" x 30" section of rebar)		
Reference Monument	S 88° W	29.00 Feet
(3/4" aluminum cap set on a 5/8" x 30" section of rebar)		

Signed by John R. Garske

Date 5/24/00

Surveyor's Michigan License No. 28410
 FB # 242, page 131



SURVEY &
MONUMENTATION

JAN 05 2001

SECTION

NORTHEAST SECTION CORNER
SECTION 14
T 47 N, R 45 W

K-5

