

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
 Gogebic County } ss.

For corners in

Gogebic
 (County)

Located In:

Corner Code #

1. Public Land Survey

T47N R45W

K-6

T ___ R

T ___ R

T ___ R

2. Property Controlling
 in Section

S ___ T ___ R

S ___ T ___ R

3. Miscellaneous
 Property in Sec.

S ___ T ___ R

S ___ T ___ R

**SURVEY &
 REMONUMENTATION**

JAN 05 2001

SECTION

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Quarter Corner common to Sections 13 & 14.

I, John R. Garske, in a field survey on April 5, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L
1											
2	6		5		4		3		2		1
3											
4	7		8		9		10		11		12
5											
6	18		17		16		15		14		13
7											
8	19		20		21		22		23		24
9											
10	30		29		28		27		26		25
11											
12	31		32		33		34		35		36
13											

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by William Burt, in 1848.

Original Corner: Cherry post

Original Bearing Trees:

10" Yellow Birch	N 70° E	12 Links
12" Yellow Birch	S 15° W	27 Links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence found.

I found an ancient fenceline running to the West and another running to the South. Wiitanen Road also runs North and East from the quarter corner location. I monumented the ¼ corner at the intersection of the ancient fence line and Wiitanen Road.

Record Research on File.

DEED GROUP APPROVED
Richard P. Dahn 5/24/00
 COUNTY REGISTER OF DEEDS

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I set a 5/8" x 30" section of rebar with a 3/4" aluminum cap at the intersection of the fencelines and road, from which I established the following witnesses:

8" Maple	N 83° W	30.55 Feet
Power Pole	S 39° E	46.95 Feet
14" Spruce	S 04° W	34.77 Feet
Reference Monument (with steel sign post)	S 44° W	35.99 Feet



Signed by

John R. Garske

Date

5/24/00

Surveyor's Michigan License No. 28410