

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
 Gogebic County } **80.**

For corners in

Gogebic
 (County)

Located In:

Corner Code #

- | | | |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey | T <u>47N</u> R <u>45W</u> | <u>K-7</u> |
| | T _____ R _____ | |
| | T _____ R _____ | |
| | T _____ R _____ | |
| 2. Property Controlling in Section | S _____ T _____ R _____ | |
| | S _____ T _____ R _____ | |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | |
| | S _____ T _____ R _____ | |

SURVEY & MONUMENTATION

JAN 05 2001

SECTION

Received for record the
2ND day of JUNE
 A. D. 1900 at 10:20 o'clock
A m., and recorded in
 Liber 7 of CORNERS

page 365
Cheryl Rupp, Dep
 Register of Deeds
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____
 Section Corner common to Sections 13, 14, 23, & 24.

I, John R. Garske, in a field survey on March 30, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L
1											
2	6		5		4		3		2		1
3											
4	7		8		9		10		11		1
5											
6	18		17		16		15		14		1
7											
8	19		20		21		22		23		24
9											
10	30		29		28		27		26		25
11											
12	31		32		33		34		35		30
13											

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by William Burt in 1848.
 Set Hemlock post at the Section Corner of Sections 13, 14, 23, and 24.
 Original Bearing Trees: 12" Red Maple N 20° W 20 Links
 12" Sugar Maple S 20° E 20 Links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found a broken up concrete monument in trail centerline from Pikka Road extended and an old fenceline running to the West. The corner location is shown on 1969 MDOT plans for US-2 and checks well with the station and offset given.

Record Research on File.

DEED GROUP APPROVED
Richard P. Deahn 5/24/00
COUNTY SUPERINTENDENT

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I accepted the above described concrete monument and replaced it with a standard Bernsten monument. From this corner I established the following witnesses:

- | | | |
|------------------------------|---------|------------|
| 4" Maple | N 46° W | 44.76 Feet |
| 10" Twin Maple | N 01° E | 41.51 Feet |
| 8" Maple | S 65° W | 72.19 Feet |
| Reference Monument w/ S.S.P. | South | 15.07 Feet |
| <i>SSP - south - 1.18'</i> | | |

Signed by *John R. Garske*
 Surveyor's Michigan License No. 28410



FB # 242, PG # 130