

DEC 15 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office } ss.
Gogebic County }

Received for record the
25th day of NOVEMBER
A. D. 1998 at 10:00 o'clock
A m., and recorded in
Liber 7 of CORNERS
on page 91
Ramona Collins Deputy
Register of Deeds

For corners in

Table with columns: Gogebic (County), Located In: (Town, Range, Section), Corner Code --#
1. Public Land Survey T46N R 45W K-1
T47N R 45W K-13
2. Property Controlling S T R
3. Miscellaneous S T R
Property in Sec. S T R

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

Section Corner 1, 2, 35 & 36: T.46-47 N., R.45 W.

I, Richard L. Drahn in a field survey on November 4, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13. A dot is marked at the intersection of column K and row 13.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 8/30/1847. Original B.T.s --- 10" Hemlock N.19 E. 26 links (17.16') --- 12" Hemlock N.15 W. 19 links (12.54') --- Hemlock 10" S.69 E. 31 links (20.46') --- 10" Maple S.61 W. 43 links (28.38') ---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Restored corner position at record bearing and distance from the remains of the third and fourth bearing trees. (the first and second B.T.s have been destroyed by road construction). The third B.T. is a very badly decayed 15-20" Hemlock stump. The fourth B.T. is now a 18-24" Red Maple stump almost completely decayed. A 10" and a 12" Red Maple sprout have maintained the integrity of the original B.T.

Corner research on file with Gogebic County records. Richard L. Drahn 11/24/98
A 3/4" iron pipe bears S.38 E. 19.55' from the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position and 8" below the westerly side of a logging road I set a 2 1/2" X 30" aluminum pipe with a 3 1/4" stamped aluminum cap and the following new reference objects:

- 8" Sugar Maple N.21 W. 45.20'
8" Sugar Maple S.45 W. 31.27'
14" Red Maple S.63 E. 37.03'
6' Steel sign rail East 18.41'
A 2 1/2" X 30" aluminum R.M. with a 3 1/4" alum cap, stamped to indicate the actual corner bears East, 17.08'



Signed by Richard L. Drahn Date November 9, 1998

Surveyor's Michigan License No. 21564