

OCT 03 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the
10TH day of JUNE
A. D. 1996 at 10:00 o'clock
A. m., and recorded in
Liber 5 of CORNERS
on page 364.
Kimona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

For corners in

Gogebic
(County)

Located In:

Corner Code ##

1. Public Land Survey

T 47N R 44W. A-7

T R

T R

T 47N R 45W. M-7

2. Property Controlling
in Section

S T R

3. Miscellaneous
Property in Sec.

S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Sec. Cor. 18, 19, 13 & 24; T.47 N., R.44-45 W.

I, Richard L. Drahn in a field survey on May 21, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on August 31, 1847. Original B.T.s --- Cedar 14" S.82 E. 28 links (18.48') --- Spruce 14" N.24 W 14 links (9.24') --- Fir 10" N.25 E. 25 links (16.50') --- Cedar 14" S.08 E. 30 links (19.80'). Corner restored by Donald D. Lappala, RLS 12585 on 10/15/70 from the stump remains of the four original bearing trees and a natural feature tie south. He set a 2½" iron pipe with a 3" stamped brass cap and the following new bearing trees: --- 14" (17" Cedar N.21 W. (N.21 W.) 18.8' (18.51') --- 14" (16") White Spruce N.55 E. (N.57 E.) 28.7' (28.41') --- 3' Elm (now dead and down) S.60 E. 13.7'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Act 74 research form on file with Gogebic County records.

Recovered the monument as described and the bearing objects as noted in parentheses above. A stump hole from the Fir bearing tree is all that remains of the original bearing trees.

BEER GROUP APPROVED
Richard L. Drahn 6/6/96
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Bearing objects referenced:

6' Steel sign rail S.25 E. 2.6 feet

6' Steel sign rail West 2.5 feet

4" X 4" Cedar post N.26 W. 2.9 feet



Signed by Richard L. Drahn

Date May 29, 1996

Surveyor's Michigan License No. 21564