

SURVEY & REMONUMENTATION

AUG 6 8 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the
13TH day of MAY
A. D. 1997 at 2:05 o'clock
P m., and recorded in
Lib. 6 of CORNERS
on page 121
Ramona Collins Deputy
Register of Deeds

Register of Deeds Stamp & File Number

For corners in

Gogebic
(County)

Located In:

Corner Code #

1. Public Land Survey

T47NR 44W A-9
T47NR 45W M-9

2. Property Controlling in Section

S T R

3. Miscellaneous Property in Sec.

S T R

4. Lot No. , Recorded Plat

5. Private Claims

Sec, Cor. comm. to sec's. 19, 30, 24 & 25

I, John P. Goss, in a field survey on April 24 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt in 1847. Set Spruce post. Original bearing trees: Y. Birch 18" - S 42° W - 23 links; Fir 10" - N 73° E - 37 links; Y. Birch 8" - S 60° E - 5 links; Fir 10" - N 65° E - 35 links. Donald D. Lappala RLS, restored this corner Oct. 13, 1969 from 3/8" iron pin and original field ties. He recorded this corner in Forest Service Records in Register of Deeds Office for Gogebic County. He established the following corner accessories:

18" White Pine N 70° E 124.1 feet (188.0 links)
W.M.P. CO. Pole No. 25- 96/97 S 15° W 109.9 feet (166.5 links)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

2 1/2" x 5' Galvanized iron pipe East 33.5 feet (50.8 links)
with 3" cap which reads: T.47N, R.44-45 W.;
S-24, S-25, S-19, S-30; 33.50 feet west;
RLS 12585; 1969.

PEER GROUP APPROVED
Richard L. Deahn 5/12/97
COUNTY REGISTER

Found the 3/8" iron pin, reference monument and bearing trees as described above. Updated the accessories as noted below to state and county specification. Act 74 research on file.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replaced the 3/8" rebar with a 2 1/2" x 30" aluminum pipe with a 3 1/4" aluminum cap stamped as follows: County Remonumentation; T.47 N.; R.44-45 W; S-24, S-25, S-19, S-30; 1997; P.S. 23509. I established the following reference objects:

23" White Pine N 70° E 122.14'
6" Poplar Due West 63.33'
W.M.P.C. P.P. #25-96/97 S 15° W 109.85'
2 1/2" I.D. reference monument East 33.50'
6' rail & sign North 1.4'
(all measurement to trees and P.Pole taken to nail in side)



Signed by John P. Goss
Surveyor's Michigan License No. 23509

Date April 25, 1997

Fed. No. R-25