

**SURVEY &
REMONUMENTATION**

AUG 6 8 1997

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

Register's Office }
Gogebic County } ss.

For corners in

Gogebic
(County)

Located In:

Corner Code #

1. Public Land Survey

T47NR 44W A- 10

T47NR 45W M- 10

T R

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

1/4 cor. comm. to sec's 25 & 30

I, John P. Goss, in a field survey on May 5, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt in 1847. Set sugar post

Original bearing trees: Hemlock 24" S 65° E 4 links
Yellow Birch 18" N 34° W 27 links

Donald Lappala, RLS, set a 5/8 inch dia. iron pin in centerline of road and record distance 1/4 mile north and south from recovered section corners. He recorded this corner in Forest Service Records in Register of Deeds Office for Gogebic County. He established the following corner accessories:

Power Pole No. 25-96/53 - S 52° W - 41.0'; 5" Elm - N 57° E - 38.5';
7" Elm - S 86° E - 31.5'; At a point 23.85' East of corner position he set a

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

2 1/2" inch dia. by 5 foot long concrete filled, galvanized pipe with 3 inch circular bronze tablet which read T.47 N.; R.44-45 W.; 1/4; S-25, S-30; R.M.; 23.85'west; R.L.S. 12585; 1970.

Found the reference monument and bearing trees as described above, I updated Accessories as noted below to state and county specification. Act 74 research on file.

PEER GROUP APPROVED

Richard P. Decker 5/12/97
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I placed a P.N. Nail in Bit. Surface at corner position and established the following references objects.

P.Pole 25-96/53 S 52° W 41.04'
6" Elm (dead) N 57° E 38.54'
7" Elm (dead) S 86° E 31.47'
11" Maple S 38° E 60.00'

R.M. (Lappala) East 23.85' & 6' rail & sign 1.4'

I set a reference monument consisting of 2 1/2" by 30" Aluminum pipe and 3/4" Aluminum cap stamped to indicate corner position.

R.M. (Goss) N 58° W 41.70' & 6' rail & sign 1.3'

Signed by John P. Goss Date May 5, 1997

Surveyor's Michigan License No. 23509

Fed. No. T-25

Received for record the
13th day of MAY
A. D. 1997 at 2:10 o'clock
7 m., and recorded in
Libor 6 of CORNERS

on page 122
Damona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

