

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Gogebic
(County)

Located In:

Corner Code #

- | | | | | | |
|------------------------------------|---|------------|---|------------|------------|
| 1. Public Land Survey | T | <u>47N</u> | R | <u>47W</u> | M-8 |
| Section 24 | T | _____ | R | _____ | _____ |
| | T | <u>47N</u> | R | <u>46W</u> | <u>A-B</u> |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |

Register's Office } ss.
 Gogebic County }

Received for record the
21ST day of OCTOBER
 A. D. 1994 at 11:15 o'clock
A m., and recorded in
 Liber 5 of CORNERS
 on page 153
Ramona Collins, Deputy
 Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

1/4 Cor. comm to sec's. 19- T47N, R46W &
24- T47N, R47W

I, John P. Goss, in a field survey on September 9, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by Wm. A. Burt in 1848. Set spruce post.
 Original bearing trees.
 Cedar 10" S27°E 10 links
 Spruce 12" N63°W 27 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Iron pin placed by Newport mine survey never found.
 Set by single proportion measurement between recorded section corners, as road construction has removed all monuments.

Act 74 research on file with County Register of Deeds Office.

PEER GROUP

Approved

Richard L. Duda 10/12/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A P.K. Nail marks the corner position from which I established the following bearing objects.

I set reference monuments #1 and #2 consisting of 2½" diameter x 30" long aluminum pipe with ¾" diameter cap stamped to note the corner position as follows:

- | | | | | |
|---------------------------|-------|---------|--------------------|-------|
| R.M. #1 | S23°E | 19.18' | - steel sign post- | 1.33' |
| R.M. #2 | S48°W | 39.15' | - steel sign post- | 1.03' |
| D.H. Nail & Tag in P.Pole | N82°E | 16.02' | | |
| D.H. Nail & tag in P.Pole | N89°W | 183.17' | | |

Signed by John P Goss Date 9-16-94

Surveyor's Michigan License No. P.S. 23509

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													



N
No Scale

