

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

Register's Office }  
 Gogebic County } SS.

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	S-31 T 48N R 46W B-13	
	S-6 T 47N R 46W B-13	
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

Received for record the  
19<sup>TH</sup> day of OCTOBER  
 A. D. 1995 at 10:10 o'clock  
A m., and recorded in  
 Liber 5 of CORNERS  
 on page 297

Ramona Collins Depetty  
 Register of Deeds  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_  
 One-quarter corner to Section 31 & 6, T48-47N, R46W

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John R. Garske, in a field survey on October 4, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- Original corner was a 12" sugar set by William Burt, D.S., on September 9, 1847. Original bearing trees: Hemlock 12" - N36°E - 20 links.
- Plat of Caribou Village recorded 1981 shows concrete monument at one-quarter corner by Duane Peterson, RLS.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

I found a concrete monument at the one-quarter corner as shown on the Plat of Caribou. Measurements to found plat corners confirm the one-quarter corner position. In addition, ties to recorded corners east and west were also used to confirm the monument as the one-quarter corner. The corner position checks with calculated position from the N-S 1/4 line as shown on the Plats of Alpine Village North and South.

(Record research on file.)

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

I replaced the 4" diameter concrete monument with a 2 1/2" diameter x 30" long aluminum pipe with a stamped 3 1/4" diameter aluminum cap from which I established the following bearing trees and/or reference objects:

- 4" S. maple - N70°W - 8.24 feet
- 6" Ironwood - N28°E - 17.96 feet
- 8" S. maple - S71°E - 25.35 feet
- 6' steel sign rail with sign - S14°W - 1.92 feet

PEER GROUP APPROVED  
Richard H. Wozniak 10/19/95  
 COUNTY REPRESENTATIVE



Signed by John R. Garske Date 10-18-95  
 Surveyor's Michigan License No. 28410