

OCT 03 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the
16TH day of AUGUST
A. D. 1996 at 10:45 o'clock
A m., and recorded in
Liber 6 of CORNERS
on page 5
Ramona Collins Deputy
Register of Deeds

For corners in Gogebic Located In: _____ Corner Code # _____
(County)

- 1. Public Land Survey T 47N R 46W _____ B-9 _____
Section 30 T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Section S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

One-quarter corner, Sections 19, 30, T47N-R46W.

I, John R. Garske, in a field survey on July 10, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by Austin Burt, D.S., on June 21, 1851. He set a wooden post from which:
12" B. ash - S71°W - 15 links (9.90')
10" Cedar - N40°E - 11 links (7.26')

- 1920's era - Gogebic County Road Commission notes indicate a corner at this position with distances of 2440.4 west and 2635.3 east.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I established the corner in the centerline of Harding Road opposite a very old and grown over trail to the south. An iron rail was found in the trail centerline on the south R/W of Harding Road. A local resident, Early "Hap" Peterson, notes that this is the generally accepted location of the corner. Measurements west (2443.87M - 2445.96 GLO) and east (2632.19M - 2640 GLO) to known corner positions were used to verify our location.

Record Research on file.

PEER GROUP APPROVED
Richard P. Drabin 8/14/96
COUNTY REPRESENTATIVE



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

The corner position is marked with a concrete nail, from which I established the following bearing trees and reference objects:

Power pole - S40°W - 40.73 feet

5" ash - N50°E - 59.13

Reference monument consisting of 2 1/2" diameter x 30" aluminum pipe with a 3 1/4" diameter aluminum cap stamped:

County Remonumentation, R.M., 1/4, T47N-R46W, S-19, S-30, 1996, 28410, S40°E, 24.96'

6' steel rail with sign 1.47 feet away.

Another reference monument is stamped as above except N42°W, 31.68' with a 6' steel rail 0.97' away.

Signed by John R. Garske
Surveyor's Michigan License No. 28410

Date 8-5-96