

SURVEY & REMONUMENTATION

JAN 22 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

For corners in
Gogebic
(County)

Located In: Corner Code #

1. Public Land Survey	Section 31	T	47W	R	46W	B-11
		T		R		
2. Property Controlling in Section	S	T		R		
	S	T		R		
3. Miscellaneous Property in Sec.	S	T		R		
	S	T		R		

Received for record the
24th day of NOVEMBER
A. D. 1997 at 11:40 o'clock
A m., and recorded in
Liber 6 of CORNSAS
on page 267
Ramona Colina Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1/4 corner sections 30 & 31, T47N, R46W

I, John R. Garske, in a field survey on October 23, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11	●											
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by Austin Burt, D.S. in 1851. He set a wood post from which:
Sugar 10" S50°W 7 links
Y. Birch 10" N5°W 27 links
Corner set @ 37.48 chains from west, total 77.48 chains; 1.52 ch. east to swamp course NNE & SSE.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

PEER GROUP APPROVED
Richard R. Decker 11/11/97
COUNTY REPRESENTATIVE

From the monumented northwest corner section 31 on the range line I measured 2470 feet (2473'R) using retracement methods to a north-south, east-west fence line intersection. The north-south fence has been repaired over the years with all fence having posts laying down. There has been logging activity to the southwest based on the fence line. I measured 100' east to a swamp/ creek which checks with the GLO call of 1.52 chains. I accepted the ancient fence line intersection as the best evidence to position the corner.

(Research on file)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I set a 2 1/2" dia. x 30" long alum. pipe with a 3 1/4" dia. alum. cap stamped to identify the corner, from which I established:

8" Spruce	N10°W	9.76 feet
8" Sugar	S70°W	12.81 feet
4" Sugar	S07°W	15.64 feet
Steel Sign Post	N58°E	1.82 feet

Signed by John R. Garske
Surveyor's Michigan License No. 28410

Date 11/11/97
No. 28410

