

OCT 09 1996

COMMISSION LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Gogebic (County)

Located In:

Corner Code #

- 1. Public Land Survey Section 31 T 47N R 46W B-148N R 46W B-146N R T T S T S T S T S T

Register's Office Gogebic County ss.

Received for record the 16th day of August A. D. 1996 at 10:45 o'clock A. M., and recorded in Liber 6 of CORNERS on page 6 Ramona Collins Deputy Register of Deeds

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat 5. Private Claims

One quarter section corner common to Sections 31 and 6, T47N, R46W.

I, John R. Garske, in a field survey on July 17, 1996 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- On September 3, 1847, William Burt, U.S. Deputy Surveyor, set a post with a: 12" hemlock - N28°E - 46 links (30.36') 30" Y. birch - N58°W - 6 links (3.96')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I established the corner position at the centerline intersection of Pioneer Road and East End Road and the centerline of an old farm lane running north. A distance of 2625.79 feet was measured east to a N-S, E-W fenceline line intersection and a distance of 2474.79 feet (2475 GLO) west was measured to the monumented corner on the Town line. Fence lines east and west at farm "40 Lines" also check well with this corner position.

Record Research on file.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corners

The corner position is marked by a 3 1/4" diameter brass cap atop a 5/8" x 24" rebar encased in concrete. The cap is stamped as follows: County Remonumentation, T47N, R46W, T46N, 1/4, S-31, S-6, 1996, R.L.S. 28410. The following bearing trees and reference objects were established:

- 2 1/2" diameter x 30" aluminum pipe with 3 1/4" diameter aluminum cap stamped: County Remonumentation, T47N, R46W, R.M., 1/4, S-31, S-6, T46N, 1996, R.L.S. 28410, N35°W, 45.31' with steel sign rail 1.60' away. Power pole - S66°W - 65.05 feet Guy pole - N60°W - 71.15 feet 8" cherry - N55°E - 75.41 feet

PEER GROUP APPROVED Richard R. Dealm 8/14/96 COUNTY REPRESENTATIVE

Signed by John R. Garske Surveyor's Michigan License No. 28410

Date 8-4-96

Grid table with columns A-L and rows 1-13. Contains numerical data points for surveying reference.

