

**SURVEY &  
REMONUMENTATION**

1993

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Gogebic  
(County)

Located In:

Corner Code ##

- |                                    |                           |            |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey Section 5    | T <u>47N</u> R <u>46W</u> | <u>C-2</u> |
|                                    | T _____ R _____           | _____      |
|                                    | T _____ R _____           | _____      |
|                                    | T _____ R _____           | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____   | _____      |
|                                    | S _____ T _____ R _____   | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____   | _____      |
|                                    | S _____ T _____ R _____   | _____      |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

**One-quarter corner common to S-5 & 6, T47N, R46W**

I, John R. Garske, in a field survey on November 30, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Survey by Austin Burt, U.S.D.S., June 18, 1851. Set post from which a 12" hemlock bears S42°E, 29 links and a 10" sugar bears N58°W, 16 links. No original evidence found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 4" concrete monument with 1/2" rebar at corner position, which has been used and accepted in the recorded plat of "Snow Summit" and many surveys of record.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set a 3" diameter stamped cap on the 4" concrete monument with 1/2" rebar stamped to read: County Remonumentation, T47N, R46W, 1/4 cor.; S-5; S-6; 1993; RLS 28410. Established the following bearing trees and reference objects:

- 10" maple - N16°W - 37.11 feet
- 14" maple - N88°W - 38.66 feet
- 5" maple - S25°E - 41.22 feet
- Concrete monument with iron rod - due north - 33.00 feet
- Steel sign post - S85°W - 4.84 feet

Register's Office }  
Gogebic County } SS.

Received for record the  
16<sup>th</sup> day of December  
A. D. 1993 at 2:25 o'clock  
P m., and recorded in  
Liber 4 of CORNERS  
on page 300.  
Betty Saari Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Signed by John R. Garske  
Surveyor's Michigan License No. 28410

Date 12/9/93

