

SURVEY & REMONUMENTATION COMMISSION
 APR 07 1995

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
 Gogebic County } ss.

Received for record the
21st day of OCTOBER
 A. D. 1994 at 11:15 o'clock
A m., and recorded in
 Liber 5 of CORNERS
 on page 149.
Ramona Collins Deputy
 Register of Deeds

Register of Deeds Stamp & File Number

For corners in Gogebic (County) Located In: _____ Corner Code # _____

| | | |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey | T <u>47N</u> R <u>46W</u> | <u>G-3</u> |
| Section 5 | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Sec. Cor. comm. to sec's. 5,6,7 & 8

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 13 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

I, John P. Goss, in a field survey on October 7, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by Austin Durt in 1851. Set Post.

Original bearing trees.

Sugar 12" S32°W 16 links
 Y. Birch 8" N57°E 40 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1/2" rebar with cap was found in 1980 survey of section 5. This rebar match the fence line to North and painted line to South and West. No original evidence of corner could be found so accepted this rebar as best location of corner.

Act 74 research on file with the County Register of Deeds office.

PEER GROUP Approved

Richard L. Drabin 10/12/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replaced the 1/2" rebar with cap with a 2 1/2" x 30" long aluminum pipe with a 3/4" aluminum cap stamped: S-5, S-6, S-7 and S-8, T47N, R46 W, 1994, P.S. 23509. I established the following bearing trees and reference objects.

| | | |
|---------------------------------|-------|--------|
| D.H. nail & tag in 10" Basswood | N80°W | 14.10' |
| D.H. nail & tag in 6" Basswood | N75°E | 14.72' |
| D.H. nail & tag in 21" Hemlock | S05°W | 17.35' |
| D.H. nail & tag in 12" Basswood | S20°E | 23.08' |
| Steel Sign Post | S02°W | 12.58' |



Signed by John P. Goss Date 10-8-94

Surveyor's Michigan License No. P.S. 23509