

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office } ss.
 Gogebic County }

Received for record the
21st day of JULY
 A. D. 1995 at 1:35 o'clock
P m., and recorded in
 Liber 5 of CORNERS

on page 268
Ramona Collins, Deputy
 Register of Deeds

Register of Deeds Stamp & File Number

For corners in
Gogebic
 (County)

Located In: Corner Code #

1. Public Land Survey Sec. 7 T 47N R 46W C-4
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____ Recorded Plat _____

5. Private Claims _____

1/4 cor. comm. to sec's. 7 & 8

I, John P. Goss, in a field survey on July 14, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 Original corner established by Austin Burt in June of 1851. Set post.
 Original bearing trees: Spruce 6" S 56° E 52 links
 Fir 8" N 54° W 49 links
 John Garske set this corner using center of road and East-West fence line in 1987. He recoded this corner in Liber 3 on page 259 of Land Corners for Gogebic County. He established the following witnesses and distance; 6" Maple- N 10° E-39.59'; 6" tw. Maple- N 55° E- 26.37'; 4"-6" Oak clump S 38° W- 37.23'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 I found a 5/8" rebar at the corner position and it checked with John Garske certification. I updated the corner monument and accessories as as noted below to state and county specification.

Act 74 reseach on file with the County Register of Deeds Office.

PEER GROUP APPROVED
Richard P. Warden 7/18/95
 COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 I placed a 3/4" aluminum cap stamped as follows over the 5/8 inch rebar buried 6" below gravel roadway: County Remonumentation; T.47 N., R.46 W.; 1/4; S-7; S-8; 1995; P.S. 23509. I established the following bearing trees and reference objects.

- 6" Maple N 10° E 39.59'
 - 6" tw. Maple N 55° E 26.37'
 - 6"-8" tw. Oak S 40° W 36.93'
- Reference Monument consisting of a 2 1/2" x 30" aluminum monument with a 3/4" aluminum cap stamped to indicate corner position:
 N 84° W- 29.98' with a 6' steel rail with sign at 1.32'



Signed by John P. Goss Date July 14, 1995
 Surveyor's Michigan License No. P.S. 23509