

Register's Office }
Gogebic County } ss.

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Received for record the
14TH day of AUGUST
A. D. 1995 at 10:10 o'clock
P m., and recorded in
Liber 5 of CORNERS

on page 290
Ramona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

For corners in

Gogebic
(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey | T <u>47N</u> R <u>46W</u> | <u>G-5</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Sec. Cor. comm. to sec's. 7,8,17 & 18

I, John P. Goss, in a field survey on July 28, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

- A. Description of original monument and accessories and/or subsequent restoration:
Original corner established by Austin Burt in June 1851. Set post.
Original bearing trees: Spruce 6" S 62° E 52 links
Fir 8" N 24° W 49 links.

John R. Garske and John P. Goss found iron rod in monument box in State Highway U.S. #2 and recorded it in Liber 3 on page 263 of Land Corners for Gogebic County in 1988. They established the following witnesses and distances: Corner of trek & Trail Building- N 14° W- 128.22'; P.P.# 80
S 56° E- 130.46'; P.P. # 4 - S 05° E- 71.83'
19

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
I found the iron rod in Monument box in State Highway #2 marking the corner position and it checked with the witnesses in John R. Garske and John P. Goss certification. I updated the corner monument and accessories as noted below to state and county specification.

Act 74 reseach on file with the County Register of Deeds Office.

PEER GROUP APPROVED
Richard H. Drahm 8/8/95
COUNTY _____



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
A iron rod in monument box marks the corner position from which I established the following bearing objects.

I set reference monuments consisting of 2 1/2" by 30" aluminum pipe with a 3/4" cap stamped to indicate corner position.
R. M. N 20° E- 118.95- 6' steel rail and sign- 1.32'
R. M. S 43° W- 46.07- 6' steel rail and sing- 1.13'
T. Pole # 80 S 56° E- 130.46'
T. Pole # 4 S 05° E- 71.83'
19

Corner of outer Edge Building. N 14° W- 128.22'

Signed by John P Goss Date July 29, 1995
Surveyor's Michigan License No. P.S. 23509