

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
 Gogebic County } ss.

Received for record the
12TH day of MAY
 A. D. 1995 at 11:20 o'clock
A m., and recorded in
 Liber 5 of CORNERS
 on page 260.
Ramona Collins Deputy
 Register of Deeds

Register of Deeds Stamp & File Number

For corners in

Gogebic
 (County)

Located In: Corner Code #

- | | | |
|---------------------------------------|---------------------------|------------|
| 1. Public Land Survey | T <u>47N</u> R <u>46W</u> | <u>C-6</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

1/4 cor. comm. to sec's. 17 & 18

I, John P. Goss, in a field survey on April 15, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by Austin Burt on June 20, 1851. Set Post.
 Original Bearing Trees:
 Cedar 8" S 59° E 8 links
 Cedar 6" N 78° W 12 links.

John P. Goss in 1991 using field notes from mining company found 2½" axle as called for in field notes. Accepted same as corner and recorded this corner in Liber 4 on page 6 of Land corners for Gogebic County: 8" Maple S08°W- 22.71'; 12" Maple-N50°W- 14.73'; 10" Maple-N57°E- 28.57'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found the car axle marking the corner position and it checked with the three (3) bearing trees in John P. Goss certification. I updated the corner monument and accessories as noted below to state and county specification.

Act 74 reseach on file with the County Register of Deeds Office.


PEER GROUP APPROVED

Richard R. Dredman 5/11/95
 COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replaced the car axle with a 2½" x 30" aluminum pipe with a 3¼" aluminum cap stamed as follows: County Remonumentation; 1/4; S-17; S-18; T.47 N.; R.46 W.; 1995; P.S. 23509. I established the following bearings trees and reference objects.

- | | | |
|----------------------|---------|--------|
| 9" Maple | S 08° W | 22.71' |
| 14" Maple | N 50° W | 14.73' |
| 12" Maple | N 57° E | 28.57' |
| 9" Maple | S 23° E | 28.47' |
| 6' Steel Rail & Sign | S 83° W | 1.91' |



Signed by John P. Goss

Date April 17, 1995

Surveyor's Michigan License No. P.S. 23509