

**SURVEY & REMONUMENTATION**

OCT 03 1996

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in <u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>47N</u> R <u>46W</u>	<u>C-9</u>
	T _____ R _____	_____
Section 20	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous	S _____ T _____ R _____	_____
Property in Section	S _____ T _____ R _____	_____

Register's Office }  
Gogebic County } ss.

Received for record the  
16<sup>th</sup> day of August  
A. D. 1996 at 10:45 o'clock  
A m., and recorded in  
Liber 6 of CORNERS  
on page 8  
Ramona Collins Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Section corner to Sections 19, 20, 29, & 30, T47N, R46W.

I, John R. Garske, in a field survey on June 18, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- Original survey by Austin Burt, D.S., in 1851. He set a wood post from which: 10" Fir - S70°W - 17 links and 16" Lynn - N58°E - 5 links.
- USFS Survey from 1935 indicates a corner found at intersection of Harding and Geneva Roads.
- Undated information from Gogebic County Road Commission indicates a corner position with dimensions, north, east and west. (See sketch on back)

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Due to road construction and farming no original corner evidence exists. I established the corner at the centerline intersection of South Geneva and Harding Roads after receiving a strong signal at this location. Measurements to known corner positions, North, South, east and west were used to verify this corner location.

**PEER GROUP APPROVED**  
Richard L. Dean 8/14/96  
COUNTY REPRESENTATIVE

(See sketch on back)

Record research on file.

I updated the corner position to state and county specifications as noted below.



**C. Description of monument for corner and accessories established to perpetuate locating the position of corner:**

At the road centerline intersection I set a 5/8"x 24" rebar capped with a 3 1/4" diameter brass cap stamped to read: T47N, R46W; 19, 20, 29, & 30, 1996, RLS 28410, cemented into the pavement from which I established the following bearing trees and reference objects:

- Light pole-S53°W-55.23 feet
- 8" Tamarack-N33°E-78.70 feet
- 10" Red Pine-S40°E-56.74 feet

Reference monument consisting of a 2 1/2" diameter x 30" long aluminum pipe with a 3 1/4" diameter aluminum cap stamped: County Remonumentation; T47N, R46W, R.M., 19, 20, 29, & 30, 1996, RLS 28410, S41°E, 52.19 feet; with a six foot steel rail with a sign-1.22 feet away.

Signed by John R. Garske  
Surveyor's Michigan License No. 28410

Date 8-4-96


SURVEY &  
REMONUMENTATION

OCT 03 1996

COMMISSION

T.47N. R.46W.  
C-9

SKETCH!



NO SCALE

R-RECORDED  
M-MEASURED

