

**SURVEY &  
REMONUMENTATION**

OCT 03 1996

**COMMISSION LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in <u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>47N</u> R <u>46W</u>	<u>C-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register's Office }  
Gogebic County } ss.

Received for record the  
16<sup>th</sup> day of August  
A. D. 1996 at 10:45 o'clock  
A m., and recorded in  
Liber 6 of CORNERS  
page 10  
Ramona Collins, Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

The section corner common to Sections 30, 29, 31, 32, T47N, R46W.

I, John R. Garske, in a field survey on July 29, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found, as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- On June 21, 1851, Austin Burt, U.S. Deputy Surveyor, set a post with the following bearing trees:  
12" Cedar - S32°E - 10 links  
8" B. ash - N75°W - 15 links

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

I established the corner in the centerline of South Geneva Road and an old overgrown trail to the east. An ancient fence line runs west from this position. I measured 2632.67 feet south and 2659.42 feet north to monumented corner positions. The GLO creek call south fits reasonably well with this position.

(See sketch on back.)

Record Research on file.

PEER GROUP APPROVED  
Richard P. Deaton 6/14/96  
COUNTY REGISTER



**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

I set a 4" stainless steel spike to mark the corner location. The following bearing trees and reference objects were established:

- A 3/4" x 8' aluminum rod with 3 1/4" aluminum cap stamped: T47N, R46W, R.M. 30, 29, 31, 32, 1996, RLS 28410, S49°W - 31.00' with a 6' steel sign rail 1.00' away.
- Another aluminum cap the same as above except N49°E - 34.26' with a steel sign rail 0.78' away.
- 4" Black ash - S65°E - 39.71 feet
- 8" Black ash - N55°E - 60.78 feet

Signed by John R. Garske  
Surveyor's Michigan License No. 28410

Date 8-4-96

SURVEY &  
REMONUMENTATION

OCT 03 1996

COMMISSION

T. 47N., R. 46W.

C-11

SKETCH

