

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
 Gogebic County } SS.

For corners in

Gogebic (County) Located In: Corner Code #

1. Public Land Survey	T <u>47N</u> R <u>46W</u>	<u>D-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	<u>Seg. #1</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Received for record the 21st day of SEPTEMBER A. D. 1995 at 9:55 o'clock A m., and recorded in Liber 5 of CORNERS on page 295.
Ramona Collins, Deputy
 Register of Deeds
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____
 One quarter corner common to Sections 7 & 18, T47N, R46W

I, John R. Garske, in a field survey on May 22, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- On June 20, 1851, Austin Burt set a wood post from which a 7" aspen bears S34°W, 6 links and a 6" spruce-N63°E, 24 links.
- Wisconsin Central Railroad maps (no date) formerly the Minneapolis-St. Paul & Sault St. Marie Railroad shows a corner position.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No corner evidence could be found due to road and utility construction. The corner position was reestablished by the single proportional method. Corner is located on line and midway between the section corners common to Sections 7, 8, 17, 18 and Sections 8, 9, 16, 17. Its location falls approximately 3 feet east of the centerline of Puritan Road approximately 120' north of the centerline of the abandoned C&NW R.R. which checks with their plans.

Corner record research on file with County Register of Deeds.

HEER GROUP APPROVED
Richard P. Whelan 9/20/95
 COUNTY REPRESENTATIVE



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

The corner position is marked by a P.K. nail, from which I established the following bearing trees and/or reference objects:

- Power Pole - S17°W - 106.50 feet
- Power Pole - N08°E - 163.72 feet
- 2 reference monuments consisting of a 2 1/2" diameter x 30" long aluminum monument with a 3 1/4" diameter aluminum cap stamped: County Remonumentation; T47N, R46W; 1/4 cor; R.M. S-8, S-17; RLS 28410; 1995. RM#1 - S65°E - 17.95 feet with a 6 foot steel rail and sign 1.10 feet away; RM#2 - N69°W - 24.48 feet with a 6 foot steel rail and sign 0.24 feet away.

SEE SKETCH ON BACK

Signed by John R. Garske Date 9-15-95
 Surveyor's Michigan License No. 28410

No Scale

SKETCH

