

SURVEY &  
REMONUMENTATION

SEP 08 1998

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogebic County } ss.

For corners in SECTION

Received for record the  
14<sup>th</sup> day of MAY  
A. D. 1998 at 3:30 o'clock  
P m., and recorded in  
Liber 6 of CORNERS  
on page 388  
Ramona Collins Dep.  
Register of Deeds

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T47NR46W</u>	<u>D-5</u>
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	<u>Sec. 2</u>
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, John P. Goss, in a field survey on March 31-19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1/4 cor. comm. to sec's. 8 & 17

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt on June 20, 1851. Set wood post.  
Original bearing trees: 7" Aspen S 34° W 6 links  
6" Spruce N 63° E 24 links

On May 22, 1995, John Garshe, P.S., re-established the corner position by single proportional method. He set a P.K. Nail in road surface with the following reference objects: P.Pole - S 17° W - 106.50'; P.Pole - N 08° E - 163.72'; 2 reference monuments: R.M. #1 - S 65° E - 17.95' & 6' rail & sign - 1.10'; R.M. #2 - N 69° W - 24.48' & 6' rail & sign - .24'.  
He record said corner in Liber 5, page 295 of Land Corners for Gogebic County,

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Said corner was removed in road construction. I added a witness to the corner P.Pole - N 11° W - 200.00', before corner was removed.

After road construction was completed, I updated the corner monument and accessories as noted below to state and county specification.

Act 74 research on file.

FIRM GROUP REPRESENTATIVE  
Richard P. Drazin 5/13/98  
COURT REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Inside a Monument box I placed a 5/8 inch by 20 inch rebar with a 3/4" brass cap which read: County Remonumentation; T.47 N., R.46 W.; 1/4; S-8, S-17; 1998; P.S. 23509. I established the following existing and new reference objects.

P.Pole #17-43/92 S 17° W 106.50'  
P.Pole #8 -50/09 N 08° E 163.72'  
P.Pole #8 - 51/10 N 11° W 200.00'  
Reference Monument consisting of 2 1/2" x 30" aluminum monument with a 3/4" aluminum cap stamped to indicate corner position:  
S 52° E, 34.18', with 6' rail & sign 1.74'.

Signed by John P. Goss

Date April 1, 1998

Surveyor's Michigan License No. 23509

Fed. No. J-7

