

1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the
16TH day of DECEMBER
A. D. 1993 at 2:25 o'clock
P m., and recorded in
Liber 4 of CORNERS
on page 302.
Betty Loran Deputy
Register of Deeds

Register of Deeds Stamp & File Number

For corners in Gogebic (County) Located In: Corner Code #/

1. Public Land Survey Section 5 T 47N R 46W E-1
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Section corner common to S-32, 33, 4 & 5, T48N, R46W and T47N, R46W

October 4 1993

I, John R. Garske, in a field survey on _____, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Survey by William A. Burt, U.S.D.S., 1847. Set hemlock post from which a 10" lynn bears N48°E, 37 links and a 10" lynn bears N49°W, 52 links. No original evidence found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I re-established the corner by using information from surveys by William Riipi, RLS, in surveying the recorded plats of Alpen Village and Creekside. Coordinate information was used by tying into the north one-quarter, center one-quarter corner and east one-quarter corner of Section 5 and then setting the northeast corner. The corner lands at the extension of a N-S fence on an E-W fence line. Remnants of a wooden hub set by Riipi in the early 70's were found at this position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2 1/2" x 30" aluminum county monument with a 3 1/2" diameter aluminum cap stamped: County Remonumentation; T48N, R46W; S-32; S-33; S-5; S-4; T47N, R46W; 1993; RLS 28410. Established the following bearing trees and reference objects:

- 11" basswood - N70°E - 7.55 feet
- 11" basswood - N79°W - 32.13 feet
- 6" sugar - N12°W - 25.00 feet
- Steel sign post - S40°E - 2.30 feet
- Center line two-track trail - due south - 21.5 feet



Signed by John R. Garske Date 12/9/93
Surveyor's Michigan License No. 28410